

MAG - Type Of DRYRUN Unit Three Phase - DOL

	Features	H L C Pump Controller	CHOTA Pump Controller	MAGIC Pump Controller
1	Manual/Auto Switch	...	Yes	Yes
2	Auto on	...	Yes	Yes
3	Auto Off	Yes	Yes	Yes
5	Low Voltage Settings	...	Option 100-300V (Motor Safety 280V)	Option 100-300V (Motor Safety 280V)
6	High Voltage Settings	...	Option 100-600V (Motor Safety Below 500V)	Option 100-600V (Motor Safety Below 500V)
4	DryRun	Yes	Yes	Yes
7	OverLoad	Yes	Yes	Yes
8	Auto Start Delay	...	Option 02-999 Sec	Option 02-999 Sec
9	Running Timer	Option 01-999Min	Option 01-999Min	Option 01-999Min
10	Restart Timer	...	Option 01-999Min	Option 01-999Min
11	Trip Time	Option 05-12 Sec	Option 05-12 Sec	Option 05-12 Sec
12	Imbalance Volt	...	Average 60-80 V	Option 40-100 V
13	Phase Sequence	...	R Y B (Check & Correct)	Auto
14	CT	1 CT	1 CT	3 CT
15	Display	LED	LED	LCD
16	Float	Yes Auto Off Only	Yes Auto ON And Off	Yes Auto ON And Off
17	GSM Option	...	...	Yes
18	Indication Lamp	Motor On	Ready	Power
		Dry Run/Tank Full	Over Load	Ready
		OverLoad/VoltageError	Dry Run	Tank Full
		...	Tank Full /VoltageError	Tripped
19	Available With Panel - Code NO	534	383	333



HLC DIGITAL CONTROLLER



SUBMERSIBLE PUMP CONTROLLER - CHOTA SERIES



SUBMERSIBLE PUMP CONTROLLER - MAGIC WATER